

OSM/LUM DECISION SHEET (DSH)

Standard(s) (incl. year)	Subclause(s)	Tracking No.	Year
IEC 60598-2-20/2010 IEC 60598-1 All editions	20.13.3 Tables 12.1 – 12.2	DSH 0965	2017
Category			
LITE			
Subject	Keywords	Developed by	Approved at
Bridging test	<ul style="list-style-type: none"> - Normal operation - Bridging test - Tables 12.1 – 12.2 	ETF5-OSM/LUM	2018 ETICS Plenary Meeting
Question			
<p>What values shall be used as limits for the temperature measured on the mounting surface during the bridging test? Is the test considered normal or abnormal operation?</p>			
Decision			
<p>According to the referred Tables of IEC 60598-1 (12.1 – 12.2), the bridging test is considered a normal operation test. Only the cable and the lampholder have to be measured.</p>			
Explanatory notes			
<p>---</p>			